


LAOLA@PITZ Experiment: Current Status

Plasma cell, Ionization laser, Diagnostics


Matthias Gross
LAOLA Workshop
Wismar, 28 May 2013

1) Self-modulation of electron beam (proof of principle for CERNs AWAKE exp.)


- use high flexibility of photo cathode laser system:




- **Example: flat-top e-beam through plasma cell:**



Peak density $\approx 10^{13} \text{ e}^-/\text{cm}^3$




Plasma density $\approx 10^{15}/\text{cm}^3$



2) Study high transformer ratio

- resonantly drive plasma wave with specially shaped electron bunch (5 bunchlets inside the bunch)

→ high transformation ratio:



to be sent to **bunch compressor**



Lithium Plasma Cell

> Principle:

- Evaporate Lithium in central pipe (700°C)
- Define beginning and end of Lithium zone with steep temperature gradient and Helium buffer gas
- Once pressure regions have stabilized:
 - Ionize Lithium gas with laser
 - Inject particle beam for PWA experiment






Figure from: P. Muggli et al. "Photo-Ionized Lithium Source for Plasma Accelerator Applications", *IEEE Trans. Plasma Science* **27** (1999), pp. 791-799

Experiments have started with Plasma Cell Prototype

- First: Measurement of temperature profile with air in plasma cell tube



- Copper tube helps to homogenize temperature distribution: $\pm 2^\circ\text{C}$ ($< 1\%$) over 10cm
- Temperature is high enough: need $\approx 650^\circ\text{C}$ in PITZ experiment

Ionization Laser for Plasma Cell Experiment at PITZ

	COMPexPro 201	CENTAURUS
Manufacturer	Coherent	Amplitude
Type	ArF	Ti:Sa
Wavelength	193nm	785nm
Repetition rate	max. 10 Hz	10 Hz
Max. pulse energy	400 mJ	100 mJ → peak power 1 TW*
Pulse duration	typ. 25 ns	<100 fs (typ. 85 fs)
Pulse to pulse stability	<1% rms	<2% rms



	COMPexPro 201	CENTAURUS
Pointing stability	$\pm 20 \mu\text{rad}$	$\pm 2.5 \mu\text{rad}$
Timing jitter	<100 ns	10 ns
Beam profile	Multimode 24mm x 10mm	Single mode $M^2 < 1.5$
Dimensions	168x38x79 cm ³	165x120x30 cm ³ on optics table
Periphery	Gas Panel	Electronics Rack
Price	86k€...92k€	330k€...350k€
Lead time	2..3 months	5..6 months

* Laser is modular – peak power can be increased to 2 TW by upgrading pump laser (30 k€)



Ionization laser coupling: ArF

- Homogeneous plasma by single beam side coupling
- Increase plasma density by multiple passes
- Estimation:
 - Li density 10^{16} cm^{-3}
 - Pulse energy 100mJ
 - Plasma channel: 1cm high, 6cm long
 - Need 3 to 4 passes to achieve plasma density of about 10^{15} cm^{-3}



Neutral Density Measurements


A. UV Absorption

- A low energy laser pulse of 5.83eV (UV) photons will be sent along the heat pipe oven axis ionizing the Li vapor through a single-photon process.
- A line-integrated neutral density n_oL can be calculated by measuring the ratio of transmitted to incident UV energy

$$n_oL = -\frac{1}{\sigma} \ln\left(\frac{E_{\text{transmitted}}}{E_{\text{incident}}}\right)$$


Where n_o = neutral density, L = Plasma column length,
 $\sigma = 1.8 \times 10^{-18} \text{cm}^{-2}$ is the ionization cross section for $h\nu = 5.83\text{eV}$

- Many shots would be required at each oven temperature and the ratio should be averaged for statistical interpretation of the outcome.




Plasma Density Measurements

B. He-Ne laser interferometry




Plasma Diagnostics with Ti:Sa Laser



> Assume: Gaussian beam

- $D_{\max} = (300+100+200+100+100)\text{mm} = 800\text{mm}$
- $r = 5\text{mm}$ (half diameter of vacuum window – worst case: put at D_{\max})
- $\rightarrow \theta_{\max} = 6\text{ mrad}$
- Lateral resolution: $2w_{0,\max} = 2\lambda/\pi\theta \approx 80\mu\text{m}$
- Calculation of axial resolution also leads to value $<100\mu\text{m}$



> High resolution 3D measurement possible

Time Plan for Plasma Cell Experiments (Self Modulation)

- > Design of plasma cell (could be preliminary) ongoing – Jun 2013
 - Mechanical structure including gas feed, heating coils, water cooling
- > Construction of plasma cell Jul – Aug 2013
- > Setup of experiment in lab ongoing – Sep 2013
 - Lithium filling
 - Test of diagnostics
- > Lab experiments Oct – Dec 2013
- > Setup of experiment in PITZ tunnel Jan – Feb 2014
- > Beamline experiments Mar 2014 – Jun 2015
 - Requirements: Availability of
 - Gun (Conditioning and Characterization work for FLASH, E-XFEL)
 - TDS (Startup, calibration)



Summary

- > PWA Experiments are planned at PITZ
 - Now: Characterization of electron beam self modulation
 - Later: High transformer ratio
- > Utilization of good diagnostics and unique laser system
- > Currently:
 - First experiments with plasma cell prototype
 - Design of plasma cell with sideports
- > Diagnostics considered at PITZ
 - UV absorption (1D gas density)
 - Interferometry (1D gas and plasma density)
 - Localized ionization (3D gas density)

