Status and future plans of PITZ

Photo Injector Test Facility at DESY in Zeuthen

Mikhail Krasilnikov for PITZ team Virtual ARD ST3 Workshop, 23.09.2020








Photo Injector Test Facility at DESY in Zeuthen (PITZ)

High brightness photo injector development, optimization and applications


- As first machine @DESY: restarted operation after COVID19 lock-down on 20.4.2020: efficiency of shift work is lower than before, e.g. due to separation of both shift persons, but → several run periods with extensive measurement program:
 - **Gun4.2** is running **stably**, usually 200 µs RF pulse length, up to 60 MV/m, >92% up time
 - Emittance reduction with truncated Gaussian
 - THz@PITZ → application of PITZ for THz SASE FEL, design finalized + several beam measurements
 - Progress on new ELLA system, also during COVID19 lock-down
 - Cathode response time measurements
 - Thermal emittance measurements at fresh and used Cs2Te cathodes
 - ...
- TDS klystron was exchanged and put back into operation
- Further installations in the PITZ tunnel annex (THz@PITZ)





THz R&D at PITZ

Developments on accelerator based THz source for pump-probe experiments at the European XFEL




LCLS-I undulators (on load from SLAC)

Properties	Details
Туре	fixed gap planar hybrid (NeFeB)
Nominal gap	6.8 mm
K-value	3.49
Support diameter / length	30 cm / 3.4 m
Vacuum chamber	11 mm x 5 mm
Period length	30 mm
Poles / a module	226 poles (= 113 periods)
Total weight w/o vac. chamber	1000 kg



Main option: THz SASE FEL

Saturation pulse energy [mJ]



Sat. pulse energy: 0.1 – 1.2 mJ


Sat. length: 3.5 – 8 m


LCLS-I undulator field measurement at DESY in Hamburg



Horizontal field gradient implementation


- Two LCLS-I undulators have arrived at Hamburg in August 2019
- The fields of the undulator L143-112000-26 have been re-measured at DESY Hamburg and are consistent with SLAC measurement (discrepancy < 0.02 T)
- However, the transverse gradient will lead to an off-axis (~25 mm) trajectory in the horizontal plane; steering coils will be considered to correct it







Design and modeling of correction coils

Horizontal undulator gradient impact onto beam transport and FEL








PITZ-4 Setup for THz generation

PITZ Beamline Upgrade for THz Proof-of-principle Experiments




PITZ-4 Setup for THz@PITZ

Beamline technical design and Infrastructure

- Layout of beam line fixed, parts are being built
- Design of screen stations and THz diagnostic setup started
- Crane installed, infrastructure setup ongoing (cabling, network and gas dis
- Personal interlock installed & tested, waiting for TÜV approval
- Magnetic field of LCLS-I undulator was measured in HH
- New support structure for undulator designed, ordered
- First stage of radiation safety concept for ser design of components (e.g. beam shutt

Simulations on radiation safety of




Jepartment in HH,




PITZ Bunch compressor

Magnetic chicane based on HERA steerers


- To optimize for SASE
 - high averaged currents, longer than cooperation length
 - high charge, longitudinal flat-top and Gaussian
- To support tuning seeded FEL (by Photocathode laser pulse modulation)
- To optimize for superradiant
 - · short bunch length
 - relatively low charge 10pC-1nC, longitudinal Gaussian
- To optimize for low-Q sub-ps high-repetition application (~1pC)



Undulator




6-22MeV/c



Conclusions and outlook:

. . .




Simulations: Anusorn Lueangaramwong

THz Radiation Diagnostics systems for PITZ-4



Design considerations are ongoing



, or

...1e:

The THz diag


- Two screen static coupling FEL radio
 - Radiation power / ¿
 - Transverse distribution polarizations
 - Spectral distributions (interferometer setup)

The THz diagnostics system in the main tunnel

- A screen station (High2.Scr3) located downstream from the chicane is used as a CTR station for electron bunch length and compression efficiency measurements:
 - Relative radiation power / energy
 - Spectral distributions (interferometer setup)

ELLA Progress

R&D on Photocathode laser system for 3D pulse shaping




Emittance measurements with truncated Gaussian pulses

Idea: transverse truncation leads to lower emittance and better efficiency (less cuttin ...


Projected emittance measurements:

- Laser temporal: 6 ps (FWHM) Gaussian
- Bunch charge: 500pC
- Gun: 6.3 MW_p (~60 MV/m)
- Electron momentum after booster: 20 MeV/c
- Beam shaping aperture (BSA) diameter: 1.3mm

Homogeneous





Truncated Gaussian



34% emittance improvement!

15% for 250 pC bunch charge







Slice Emittance Measurements at PITZ

Slit scan with TDS and quads applied


- Method
- Challenges
- Recent results



Cathode Response Time measurements

Measuring electron bunch lengthening during emission

- Method (single shot, interferometer in Pharos, ...)
- Challenges (low charge, thorough beam transport/focusing...)
- Recent results: Cathode response time measurements ne for 5 Cs2T (5, 10, 15 nm from INFN, 10nm fresh and used free and 2 metal cathodes (Mo and Au)




(Near) Future Plans: Gun5 at PITZ


Gun5 fabrication, installation and tests

- Gun5 allowing longer bunch trains for FLASH and XFEL has high priority to reach longer RF flat-tops (up to 1 ms) for providing more bunches to users at FLASH and European XFEL.
- New cavity design (elliptic shape including cathode hole transiti extended cooling)
- Further developments of the LLRF system (**RF** pic'
- Due to COVID-19 workflows had to be rec communication etc.)→ slow progre Status:
 - RF-surface for catt
 - Stainless steel jac delivered for final n
 - Vacuum flanges wait
- Timeline:
 - ??September: final bra.
 - ??October: start of set u

ຼປຣ, tuning → dry ice cleaning,

∠euthen, installation at PITZ







d cathode

Central iris part with outer machining before brazing stainless steel jacket

Conclusions and Outlook

Status and future plans of PITZ

Thank you

Plan of the Talk

+ Speed talks proposals



- Short introduction to PITZ facility (1-2 slides):
 - operation during COVID-19
 - main current activities
- THz at PITZ project progress (5-6 slides):
 - Introduction (proof of principle for pump-probe THz source) =1 slide
 - LCLS-I undulator measurements in Hamburg, horizontal gradient modeling, compensation coil design) =2 slides
 [Speedtalk?]



- Bunch compressor design = 1 slide → Anusorn [Speedtalk?]
- THz diagnostics design = 1 slide → Prach [Speedtalk?]
- ELLA progress =1 slide → Christian
- Truncated Gaussian shaping =1 slide → Matthias [Speedtalk]
- Slice emittance =1 slide → Raffael
- Cathode response time (1-2 slides) → Houjun, Gregor, Ye [Speedtalk?]
 - Setup
 - Highlight results
- Upcoming: gun5 highlights and installation plans = 1 slide → Sebastain (+Frank)
- Conclusions and outlook = 1 slide

