



Status of PAL-XFEL & Injector Development


Jang-Hui Han
Pohang Accelerator Laboratory

PI 16 October 2013

- PAL-XFEL project overview
 - Layout
 - Schedule & Status
 - Components development

- PAL-XFEL Injector

Location of Pohang Accelerator Laboratory



PAL-XFEL Project



- The project started in 2011 aiming at construction by 2014
- Building construction ongoing
- Commissioning to start in 2015




View of the Construction Site



Aerial view on 28th August 2013


Schedule



Linear Accelerator & Undulator



- 10 GeV S-band normal conducting linac
- 1 hard & 1 soft X-ray undulator beamlines
(space for two more hard and one more soft lines reserved)
- 60 Hz repetition rate with single or two micro bunches



Accelerating Structure

- Potential providers: Mitsubishi Heavy Industries, IHEP, RI ...
- PAL developing structures with a domestic company
- High power test of prototypes ongoing at ATF

Operation frequency	2856.00MHz (30 °C, in vacuum)
Accelerator type	Constant-Gradient, Traveling-Wave
Operation mode	$2\pi/3$
Attenuation constant	0.57 neper
Shunt impedance	$\geq 53\text{M}\Omega/\text{m}$
Filling time	$\sim 0.83\mu\text{s}$
Q	>13000
Phase error	$\Sigma\theta_i < \pm 2.5\text{deg}$
Operation temperature	30 °C \pm 0.1 °C
Overall length	3.120 (acceleration length 2.91475) m



High power test at ATF

Accelerator & Modulator Test Facility




High power RF source for
accelerator components

Modulator test stand



RF Components Production & Test





Energy Doubler (SLED)

Test of SLED



Cavity BPM: sub- μm e-beam Position Monitor




Undulator Prototype



Hard X-ray undulator


- 5 m long planar
- Variable gap
- 18 undulators to be installed at HX line initially

Prototype of ID chamber and Intersection



Length=6m


Inner gap=6.8mm





PAL-XFEL Gun 1



- Developed by PAL & POSTECH since 2005
- Design based on BNL S-band gun
- 1.61 cell & side coupling with 2 RF and 2 pumping holes
- Beam commissioning ongoing at ITF




PAL-XFEL Injector - Based on Gun1



- Injector length: 9 m → 12.3 m
- RF station: 1 × 25 MW, 2 × 80 MW → 2 × 25 MW, 1 × 80 MW

Baseline 1

- **Gun1**
- **Gun solenoid** at 205 mm from cathode (no magnetic field compensation solenoid)
- **2 accelerating sections with 2 focusing solenoids**
- 120 MV/m max field at cathode, 5.7 MeV beam energy at gun exit
- **20 MV/m gradients at 1st accelerating tubes, 25 MV/m at 2nd tube**
 → **139 MeV beam energy at injector end**
- 1st accelerating section starts at 2.2 m from the cathode
 (longer e-beam focal length due to the smaller laser beam at cathode)
- No quadrupoles for keeping the beam transverse shape to be circular through the injector



Beam Parameters of Baseline 1 Injector





Cathode laser

Longitudinal shape:


- 8 short Gaussian pulses stacked
- 8 ps fwhm

Transversely uniform





200 pC beam simulation at injector end
→ 0.26 mm mrad transverse projected emittance


Beam Parameters of Baseline 1 Injector



200 pC



PAL-XFEL Injector – Based on Gun2




- RF gun change
- RF station: 1 × 25 MW, 2 × 80 MW → 2 × 25 MW, 1 × 80 MW

Baseline 2 Injector (updated Spring 2013)




- **Gun1**
- **Gun solenoid** at 205 mm from cathode (no magnetic field compensation solenoid)
- **3 accelerating sections with 2 focusing solenoids**
- 120 MV/m max field at cathode, 5.7 MeV beam energy at gun exit
- **9 MV/m gradients at 1st accelerating tubes, 17 MV/m at 2nd and 3rd tubes → 132 MeV beam energy at injector end**
- 1st accelerating section starts at 2.2 m from the cathode (longer e-beam focal length due to the smaller laser beam at cathode)
- No quadrupoles for keeping the beam transverse shape to be circular through the injector




Beam Parameters of Baseline 2 Injector



Emittance at central slices ~ 0.2 mm mrad




Peak current 25 A



PAL-XFEL Gun2




- Developed by PAL since 2012
- Design based on Diamond S-band gun which is based on PITZ L-band gun
- 1.54 cell & coaxial coupling
- Cold test ready
- Beam commissioning planned in 2014



Alternative Injector (for lower Emittance)




- Gun2
- Gun solenoid at 105 mm from cathode with a bucking solenoid
- **3 accelerating sections with 2 focusing solenoids**
- 120 MV/m max field at cathode, 5.3 MeV beam energy at gun exit
- **9 MV/m gradients at 1st accelerating tubes, 16 MV/m at 2nd and 3rd tubes → 125 MeV beam energy at injector end**
- 1st accelerating section starts at 1.7 m from the cathode
- No quadrupoles for keeping the beam transverse shape to be circular through the injector




Beam Parameters of Alternative Injector




Emittance at central slices ~ 0.12 mm mrad



Peak current 22 A



Injector Test Facility (ITF)



Tunnel




Gallery




Baseline gun


First Results from ITF



For 0.35 mm laser size (full radius)
95% emittance: 0.41 / 0.48 μm in X / Y



Laser beam profile



parameter	Value
Beam energy	135 MeV
charge	200 pC
Gun phase (laser injection)	35 degs
Accelerating column phase	on-crest (both)

Thanks

